

APR 08 1999

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw
(County)

Located in:

Corner Code #

1. Public Land Survey

T	21N	R	01E	A-1
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

LIBER 3 PAGE 197
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

23 DEC 1998 3:45:07 P

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Timothy L Lapham, in a field survey on September, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

A-1: GLO 1837 J Brink, set post
Yellow Pine 18 S74-1/2W 43 (1)
Yellow Pine 18 N71W 68

GLO 3/15/1838 L Clason
Yellow Pine 20 N17E 77
Yellow Pine 24 S32E 55

Survey 1920+/- M. Schaaft
DNR records indicate that he found or established and replaced this corner but exactly what was done in not known. No notes or accessories are available.

Survey 5/1967 G Henning
set from original USBT
16" W. Oak N59W 42.4' (2)
16" W. Oak N52E 46.2' (3)
10" B. Oak S52W 64.8' (4)

Survey 9/24/1982 R. Higgins
1/2"x40" pipe found with 1/2"x18" bar set inside
Duplicate of (2) above
Duplicate with slightly different bearings of (3) and (4)
11" Oak S64E 22.4' (5)

Approved by Peer Review

12/15/1998
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-1: Found 1/2"x18" rerod with cap No. 21570. The rerod is 9'+/- west of the P.I. of trails north and west and 3'+/- west of a trail south.
Found: remains of old stump of (1), good stump of (2), living trees (3) and (5). Accepted found iron as perpetuation of Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-1: Set 5/8"x36" rerod with aluminum Ogemaw county remon cap flush with ground.

Witnesses:
S61E 22.39' NAIL IN 16" OAK
N54E 46.43' NAIL IN 18" OAK
N15W 39.02' NAIL IN TWIN 8" CHERRY
S38W 16.60' NAIL IN TWIN 12" OAK
EAST 15'+/- carsonite post



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/21/98