

APR 08 1999

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw (County) Located in: Corner Code #
1. Public Land Survey T21N R01E A-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

LIBER 3 PAGE 196
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

23 DEC 1998 3:44:54 PM

WANDA WUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Timothy L. Lapham, in a field survey on September, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at row 3, column B.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

A-3: GLO 2/13/1837 J. BRINK POST
BEECH 8" S37W 33LK
MAPLE 9" N76W 06LK

GLO 5/27/1846 B.F.HALL FOUND POST
W. PINE 14" S12E 21LK
SUGAR 6" N15E 28LK

GLO 8/26/1850 G H CANNON FOUND POST
NO ADDITIONAL WITNESSES

DNR CIRCA 1920 M. SCHAAF - RECORDS INDICATE THAT CORNER WAS FOUND BUT NOT REPLACED BUT RECORDS DO NOT SHOW ANY CORNER MATERIAL OR WITNESSES

ROSCOMMON CO. L2-LCRC-P11 DATE AND SURVEYOR
UNKNOWN
1/2" IRON IN CENTERLINE ROADS
S56E 41.0' 8" R. OAK (1)
S37W 38.5' 4" TW. MAPLE
N64W 43.5' 8" R. OAK (2)

SURVEY 11/6/1961 G HENNING
1/2" IRON BAR IN CENTERLINE ROADS AT INTERSECTION
FIRE LANES WITH SAME ACCESSORIES AS ROSCOMMON
LCRC 2-11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3: FOUND 1/2"x18" REROD IN APPROXIMATE CENTERLINE OF TRAILS N-S-W. MATCHES PREVIOUS WITNESSES (1) AND (2).
ACCEPTED IRON AS BEST AVAILABLE EVIDENCE OF CORRECT CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3: Set 5/8"x36" rerod with aluminum Ogemaw County remon cap to 6" below grade.(road is being eroded by vehicles)

Witnesses:

S53E 41.22' NAIL IN 10" OAK (OBT)
N50E 40.92' NAIL IN 8" MAPLE
N13W 52.37' NAIL IN 18" OAK
N59W 43.43' NAIL IN 18" OAK (OBT)
EAST 8'+/- carsonite post

Approved by Peer Review

12/15/98 DATE INITIALS



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/21/98