

APR 08 1999

Ogemaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T21N R01E	A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 3 PAGE 192

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

23 DEC 1998 3:44:01 PM

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

A-7: GLO 2/13/1837 J Brink set post Hemlock 12 S41W 55 Hemlock 12 N31-1/2W 8	Roscommon Co. LCRC 2-12 date and surveyor unknown 1-1/2" pipe 4" R Maple N81E 25.5' (1) 5" R Maple N39E 21.5' (2) 7" R Maple N65W 4.1' (3) 12" R Oak S14W 3.0 (4)	On fence N North 42' Fence E-W
GLO 5/26/1846 B F Hall found post Beech 20 N31-1/2E 19 Beech 5 S43E 36	Survey 11/6/1961 G Henning Found 1-1/2" pipe and old post Accessories same as Roscommon LCRC 2-12	Ogemaw Co. LCRC 3-107 12/12/1989 D Ledy 1-1/2" pipe - same accessories as Ledy section break
GLO 8/27/1850 G H Cannon found post No additional accessories	Sec. Break 1989-90 D Ledy -2" pipe NNW 21.35' spike in 8" Twin Maple (5) NNE 4.58' spike in 8" Maple (6) SE 13.71' spike in 6" Maple (7)	Sec. Break 4/12/1995 D Ledy No corner material or witnesses
DNR circa 1920 M Schaaf Records indicate corner found but not replaced, no corner material or witnesses available		Approved by Peer Review <u>12/15/98</u> <u>TLL</u> DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7: Found 1-1/2" pipe 2' above grade, drove pipe down to 8" above grade. Pipe is at fence line north. Witnesses found: it appears that the distances on (5) and (6) have been switched with that in mind, (2) and revised (6) are the same with the tree living; (3) and revised (5) are the same with the tree living; and (4) and (7) are both living trees. Accepted the found pipe as the best evidence of the correct location of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7: Set 5/8"x36" rod with aluminum Ogemaw County remon cap inside found pipe.
Witnesses:
N41W 4.44' NAIL IN 8" TWIN MAPLE (OBT)
N40E 21.26' NAIL IN 8" MAPLE (OBT)
S44E 13.89' NAIL IN 8" MAPLE (OBT)
S01E 3.81' NAIL IN 30" OAK (OBT) NOTE: BEARING TO NAIL ON EAST FACE OF TREE, APPROXIMATELY S15W TO CENTER OF TREE
North 2'+/- carsonite post

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/21/98

