

**SURVEY &
REMONUMENTATION**

APR 08 1999

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

LIBER **3** PAGE **189**

_____ Ogemaw _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T21N R01E	A-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

23 DEC 1998 3:43:07 PM

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on September, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5		4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

A-10: GLO 2/12/1837 J Brink set post
Hemlock 8 S40W 15
W Pine 9 N50W 21

Witness Sheet 1985 D Ledy
Accessories same as Ogemaw LCRC 1-152

Ogemaw Co. LCRC 1-152 3/12/1976 N Caldwell
set 1/2" bar and cap in 3/4" pipe
S24W 21.8' 9" R Oak (1)
N57E 41.7' 8" Cherry (2)
S40W 9.90' Remains of 8" Hemlock (3)

Survey 3/11/1976 N Caldwell
Accessories same as Ogemaw LCRC 1-152

Sec. Break not dated from Wade Trim
no corner description or accessories

Approved by Peer Review

12/15/98 TL
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10: Found 1/2" rod inside 3/4"x18" pipe. Witnesses: (2) found dead stub; (3) found remains of stump with species undeterminable. Accepted found iron as perpetuation of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10: Set 5/8"x36" rod with aluminum Ogemaw county remon cap.
Witnesses:
N37W 21.60' NAIL IN 18" MAPLE
N34E 31.22' NAIL IN 24" MAPLE
N87E 21.71' NAIL IN 10" MAPLE
S05E 9.05' NAIL IN 10" ASH
South 1'+/- carsonite post



Signed by *Timothy L. Lapham*
Surveyor's Michigan License No. 27595

Date 12/21/98