

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 FEB 24 2000

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T21N R01E	J-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SECTION



3006798
 Page: 1 of 1
 12/27/1999 09:09A
 L-4 P-7
 Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-9: GLO by B.F. Hall, 1846, Post
 N78W 19 16" Beech
 S16E 11 3" Beech

Unrecorded survey by L. Cavanagh, 1974, not referenced

Unrecorded survey by L. Cavanagh, 1974, no material

Survey by D. Ledy, 1984, found 5/8" rod
 Northeast 45.40 20" Maple
 North Northeast 46.96 12" White Birch
 Southeast 25.26 Rd Sign Post

County Road Plans, 1999, found 5/8" rod
 N28E 25.09 10" Birch
 S04E 68.97 St Sign
 S50W 44.97 Tele Riser
 N75E 43.56 14" Twin Maple
 2540.52 J-9 to K-9

Section break by J. Richardson, 1960, found 1" bar
 No witnesses

Section break by L. Cavanagh, 1970, found 1/2" bar
 N32E 22.75 6" Birch
 S42W 42.1 Fence Cor Post

Approved by Peer Review

12-16-99 LLK
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9: No GLO evidence found. No iron or record witnesses found. Reset corner from Cavanagh 1970 section break and 1999 county road plans. Position closely matches 1960 Richardson section break. Accepted re-established position as best evidence of corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9: Set 5/8"x36" rerod w/aluminum remon cap
 North 18.69 Sign
 S10E 68.58 Stop Sign
 South 67.1 Edge of Pavement
 S45W 44.30 Tele Pole
 West 83.30 End of Pavement
 West 480.46 1/2" Rerod

Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/23/1999