

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 FEB 24 2000

For corners in

SECTION

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T21N R01E	K-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Timothy L. Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- K-9: GLO by B.F. Hall, 1846, 12" Hemlock N75W 135.69 Utility Pole
- Survey by L. Cavanagh, 1974 Found pavement box East 2.32 Centerline of Road
- Survey by R. Higgins, 1979, Found pavement box No witnesses
- Survey by D. Ledy, 1985, Found 3/8" Iron in pavement box S80W 88.4 Power Pole S76E 68.4 Power Pole East 2.52 Centerline of Road West 19.0 S.P.
- Survey by D. Ledy, 1984, Found 5/8" Iron in box WNW 132.13 Power Pole ENE 117.18 Power Pole SW 52.91 4x4 Post East 2.3 Centerline of M-30
- Survey by D. Ledy, 1985, Found 5/8" Iron in box WNW 152.13 Power Pole ENE 117.18 Power Pole SW 52.91 4x4 Post East 2.3 Centerline of M-30
- County Road Plans, 1999, Found 5/8" Iron in mon box N89E 98.27 Utility Pole S60E 67.47 Tele Ped S73W 133.97 Utility Pole
- Survey by D. Ledy, 1995, Found 5/8" rod in mon box S60E 65.9 Centerline of Bell Box N60E 117.3 Power Pole East 2.5 Centerline of M-30 Paving N60W 150.6 Face of Power Pole
- Survey by T. Lapham, 1997, Found 5/8" Iron in mon box East 2.5 Centerline of M-30 N84E 98.27 Utility Pole S60E 67.47 Centerline of Tele Pole S63W 133.97 Utility Pole N75W 135.69 Utility Pole
- Survey by T. Lapham, 1995, Found 3/8" Iron in mon box S80W 88.4 Power Pole S76E 68.4 Power Pole East 2.52 Centerline of Road West 19.0 S.P.
- Survey by B. Woods, 1996, Found rod in mon box Set bar and cap 60' East and 33' South
- MDOT plans circa 1960, No material East 2.32 Centerline M-30

Approved by Peer Review
 12-16-99 JLL
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9: No GLO evidence found. Found 5/8" iron in mon box. Iron is in accord with MDOT plans and all surveys of record. Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-9: Set 5/8"x36" rerod w/aluminum remon cap S73W 133.97 Utility Pole N75W 135.69 Utility Pole East 2.3 To Centerline of M-30 S60E 67.47 Tele Pedestal

Signed by Timothy L. Lapham
 Surveyor's Michigan License No. 27595

Date 12/23/1999

