

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 RECORDING

FEB 24 2000

SECTION

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T21N R01E	L-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	



3006777
 Page: 1 of 1
 12/27/1999 09:09A
 L-3 P-288
 Wanda Muzik, Ogemaw Co. Registrar SURC 9.00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	H
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-9: GLO by B.F. Hall, 1846, Post
 N65E 13 10" Hemlock
 S15E 13 8" Hemlock

Survey by B. Woods, 1996, Found 1/2" rod
 No Witnesses

Survey by D. Ledy, 1985, Set 5/8" rod at split on line
 NW 42.60 10" Poplar
 SW 30.60 10" Poplar
 NNE 23.87 6" Maple Clump
 NE 29.35 6" White Birch

Survey by T. Lapham, 1995, Found 5/8" Iron
 NW 42.60 10" Poplar
 SW 30.60 10" Poplar
 NNE 23.87 6" Maple Clump
 NE 29.35 6" White Birch

Survey by D. Ledy, 1995, Found 5/8" rered
 S45W 30.65 10" Poplar
 N20E 30.77 8" Maple
 N70W 43.15 14" Poplar

Approved by Peer Review


12-16-99 YLR
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9: No evidence of GLO survey found. Found 5/8" iron bar in accord with all witnesses of record. Distance to K-9 measures 2850.91 with survey record distances varying from 2650.94 to 2651.17. Accepted found iron as best evidence of corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9: Set 5/8"x36" rered w/aluminum remon cap
 N21E 95.30 6" Ash
 S21W 49.14 6" Maple
 S48W 74.59 8" Poplar
 N10W 105.02 10" Poplar



Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/23/1999