

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 21NR 1E	M-1
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 3 PAGE 16

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

28 DEC 95 3:17 P.M.

WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Timothy L. Lapham, in a field survey on December, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-1: GLO Clason 1838 Set Post, 12" Beech S43E 38lnks, 10" Beech N32W 37lnks;
Plat Henning Hillcrest Subdivision (Rec 9/23/65, 4-43), No Cor Mat, No Wits;
Survey M.S.H.D. 10/65 (Rec 1-83, 2/23/77), Found Boat Spike, 4 Wits, references as Henning Corner;
Survey Higgins 4/26/78 (Rec 2-432, 5/4/78), No Cor Mat, 2 Wits;
Survey Higgins 6/13/78 (Rec 2-519, 10/31/78), No Cor Mat, No Wits;
Survey Ledy 6/22/83 (Rec 3-457, 3/20/84), No Cor Mat, No Wits;


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1: No evidence of GLO survey found. Found Boat Spike and 3 MSHD wits; Corner in accord with Higgins survey. Accepted found corner as best evidence of the accepted position of corner. See dossier for additional information.

APPROVED BY
PEER REVIEW
12/20/95
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1: Set 5/8"x36" rorod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1995"
From which:
East 31.37' Fence Corner w/spike and MSHD cap
S60W 52.32' 21" Oak
S88W 4.05' R.R.Spike
N62W 68.72' 14" Ash
N32W 43.93' Spike in Power Pole



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/28/95