

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **3** PAGE **19**

STATE OF MICHIGAN
 Ogemaw County
 RECORDED

28 DEC 95 3:19 P.M.

WANDA HUZIK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Ogemaw
 (County)

Located in: Corner Code #

1. Public Land Survey T 21N R 1E M-4
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Timothy L. Lapham, in a field survey on December, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4: GLO Clason 1838, 8" Birch for Post;
 Unrecorded Survey Higgins, 10/13/77, Found 1/2" Bar, No Wits. On fence West, Dist to SE Cor of Sec 12 (South) 2516.57;
 Unrecorded Survey Lapham, 10/25/95, Set CI by SPM, 4 Wits;


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4: No evidence of GLO survey found. Did not find iron reference by Higgins. Found Lapham CI and all Wits. Contacted Higgins and after discussion he agreed that fence appeared to be incorrect and agreed to Lapham corner position. Fence is midway between Rau and Lehman Roads. Accepted found iron as best evidence of the accepted position of the corner. See dossier for additional information.

APPROVED BY
 PEER REVIEW
 12/20/95 *TL*
 DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4: Set 5/8"X36" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1995"
 From Which:
 N56E 108.40' 38" Willow with nail
 S44W 67.10' 6" Twin Cedar with nail
 West 6.20' Centerline of George Lake Road
 N32W 65.44' Fence Corner with nail



Signed by *[Signature]*
 Surveyor's Michigan License No. 27595

Date 12/28/95