

FEB 24 2000

Ogemaw County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw  
(County)

Located In:

Corner Code #

*Sec. 2*

1. Public Land Survey

T21N R01E M-9

T	R	
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

2. Property Controlling In Section

3. Miscellaneous Property in Sec.

**3006787**  
Page: 1 of 1  
12/27/1999 09:09A  
L-3 P-298  
Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-9: GLO by Clason, 1838, Post  
S43W 7 8" Cedar  
N67W 8 10" Cedar

DNR Survey by Roser, 1995, Fd spike  
Accepted spike

LCRC by T. Lapham, 1995, Set iron  
N58E 89.77 Power Pole  
S58W 34.72 Tele Pedestal  
S82W 74.18 10" Ash  
N32W 79.35 10" Poplar

Road Plans, 1999  
Distance to B-9 (T21N, R2E) 2848.79

Approved by Peer Review

12/16/99 [Signature]  
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9: No GLO evidence found. No corner or witnesses from 1995 remon corner found. Reset corner from remon distance North and South, road plans distance East and previous section work distance West. Accepted reestablished corner as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9: Set 5/8"x3/8" rerod w/aluminum remon cap  
N53E 59.58 Utility Pole  
S50E 85.04 8" Poplar  
S85W 74.38 10" Elm  
N34W 91.95 4" Birch



Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/23/1999