

SURVEY & REMONUMENTATION

JUL 23 1997

COMMISSIC

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw
 (County)

Located in:

Corner Code #

- | | | | | | | |
|------------------------------------|---|-----------|---|------------|-------|-----------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling In Section | S | <u>24</u> | T | <u>21N</u> | R | <u>1E</u> |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous | S | _____ | T | _____ | R | _____ |
| Property in Sec. | S | _____ | T | _____ | R | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 3 PAGE 23

STATE OF MICHIGAN
 OGEHAW COUNTY
 RECORDED

28 DEC 95 3:21 P.M.

WANDA MUZIK
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Timothy L. Lapham a field surveyor on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO Clason 1838 Set Post for Meander corner at 78.58 chains;
 Unrecorded Survey, Henning 1942, MC is 93.7' South of Corner;
 Unrecorded Survey, Richardson, No Date, MC is 93.7' South of Corner;
 Unrecorded Survey, Cooke, 1944, No Cor Mat, No Wits;
 Plat, Lake George subdivision, Richardson, 4/21/1961(Rec. 3-54) no cor mat, no wits.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO survey found. Found brass DNR capped iron. Matches Richardson dista south and plat position. Accepted found iron as best evidence of the position of the corner. See dossier for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Concrete post with reinforcing and brass DNR cap for Meander Corner
 From Which:
 N62E 33.49' 10" Cedar with nail
 S73E 30.27' 6" Cedar with nail
 S35E 37.36' 3" Poplar with nail
 S13E 8.95' Fence Post with nail
 North 19.10' Waters Edge

Signed by [Signature]

Date 12/28/95

Surveyor's Michigan License No. 27595