

SURVEY & REMONUMENTATION

MAR 19 1998

OGEMAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw
(County)

Located in:

Corner Code #

1. Public Land Survey

T 21N R 1E M-10
T 21N R 2E A-10

2. Property Controlling in Section

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

LIBER 3 PAGE 154

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

26 Dec 1997 2:59:47 PM

WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Timothy L. Lapham, in a field survey on December 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4		3		2	1
3												
4	7			8			9		10		11	12
5												
6	18			17			16		15		14	13
7												
8	19			20			21		22		23	24
9												
10	30			29			28		27		26	25
11												
12	31			32			33		34		35	36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1837 L. Clason set post
- B. Ash 8" S24W 20Lk
- Hemlock 12" N25W 28Lk
- 1993 Lapham Survey (N933212)
- No corner set. Presumed on S.P.M. between A-9 and A-11
- Overall dist. 5171.31
- 1995 Roser Survey (FM-01-91) and LCRC (L3, P53)
- 1995 Roser LCRC (L3, P53)
- Set DNR post
- 8" cedar N40W 53.3
- 15" ash N65E 22.3
- 10" cedar S25E 27.4
- 6" ash S25W 5.9
- Old W.W. N-S fence East 26'

1995 Ledy Survey (L6, P175)
Survey does not show corner
Survey based on same position as 1993 Lapham survey

1997 Lapham Survey (N965716)
Survey does not show corner
Survey based on same position as 1995 Roser LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner found. 1995 Roser DNR post found. Corner is 57' +/- South of position used for 1993 Lapham survey and 1995 Ledy survey, and is as used in 1997 Lapham survey. Found post matches N 1/8 line fence position shown in 1993 Lapham survey. North position is based on rejected M-11/A-11 corner position. Rejected North position and accepted DNR post. No fences East or West, N-S fence 26' East. Found all DNR witnesses, accepted found DNR post as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- DNR pipe and Cap
- N40W 53.3 8" Cedar
 - N65E 22.3 15" Ash
 - S25E 27.4 10" Cedar
 - S25W 5.9 6" Ash
 - East 26' Old W.W. N-S fence

Approved by Peer Review

12/14/97 [Signature] [Initials]

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/24/97

