

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

For corners in

Ogemaw
(County)

Located in:

Corner Code #

SECTION

1. Public Land Survey

T21N R02E

B-9

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R



3006914

Page: 1 of 1
12/29/1999 10:05A
L-4 P-34

Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

B-9: GLO by B.F. Hall, 1848, 12" Cedar

- County Road Plans, 1998, Found 5/8" Iron
- N15E 84.68 6" Poplar
- N69E 63.07 Utility Pole
- South 53.55 Fence Post
- S48W 63.94 1/2" Iron Rod

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Approved by Peer Review

12/29/99 JLR
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9: No GLO evidence found. Reset corner from 1998 road plan witnesses. Distance to C-9 measured 2869.48' compared to road plans calling for 2869.75'. Distance to A-9 measures 2848.71' compared to road plans calling for 2848.79'. Distance to A-9 measures 2848.71' compared to road plans calling for 2848.79'. GLO distance for entire mile is 151.21' longer than measured. Found iron is on fence line North and South. It also places East 1/8 line within 2' of fence lines North and South. GLO stream call is obviously in error (over 700' East of actual location). Setting corner by S.P.M. would upset occupation, therefore accepted re-established corner position as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-9: Set 5/8" x 3/8" rerod w/aluminum remon cap
- N15E 84.68 6" Poplar
- N69E 63.07 Utility Pole
- S40E 44.38 Gate Post
- S2W 38.76 Fence Cor Post



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/99