

SURVEY & REMONUMENTATION

MAR 19 1998

OGEMAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 3 PAGE 143

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

26 Dec 1997 2:55:55 PM

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 2E	E-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L. Lapham, in a field survey on November 20 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO B.F. Hall 1846 set post
Cedar 10" S35W 25 lk
B. Ash 9" S8E 17 lk
intersects 10 lk W of standard post

T. Lapham 1985 Survey (N850326)
Set capped iron
S75E 64.91 Power Pole
N55E 65.13 Power Pole
N40W 43.83 SE cor Tele Pedestal
East 6.60 SW cor Sec 33, 22N, 2E

T. Lapham 1989 Survey (L4, P266)
Found capped iron, same witnesses
as 1985 Lapham survey

D. Ledy 1989 Survey (L4, P377 & L5, P39)
Found iron w/ cap, same witnesses
as 1985 Lapham survey

T. Lapham 1995 Survey (N954871)
Found capped iron, same witnesses
as 1985 Lapham survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner. Found 1/2" capped iron (# obliterated) 6.60' West of second 1/2" iron in centerline of road E-W (paved). East iron in approximate centerline of gravel road North. Very old fence, mostly gone, approximately 1' East of West corner going South. No evidence of corner post remains. West iron used for corner. East iron matches 1941 position for standard corner and was accepted as such by peer review. 1985 Lapham witnesses in place.

Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1997"
S52E 64.96 Anchor Pole
N66E 65.11 Power Pole
N46W 44.1' Centerline top of telephone pedestal
East 6.60 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap
N58E 52.5 Centerline top of telephone pedestal
S01W 33.10 1/2" capped iron (Lapham)

Approved by Peer Review

11-20-97 *WML*
DATE INITIALS

Signed by *Timothy L. Lapham*
Surveyor's Michigan License No. 27595

Date 12/24/97

