

SURVEY & REMONUMENTATION

MAR 19 1998

OGEMAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
 For corners in

<u>Ogemaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T21N R 2E	G-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 3 PAGE 134
 STATE OF MICHIGAN
 OGEMAW COUNTY
 RECORDED

26 Dec 1997 2:52:14 PM

WANDA MUZIK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Timothy L. Lapham, in a field survey on November 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO B.F. Hall 1846 set post
 Maple 12" S11E 30 lk
 Beach 8" S41W 36 lk
 19 lk W of standard post

Ledy 1992 LCRC (L3-P7)
 Referenced in witness to G-13; 22N 2E
 as 12.3 West of G-13

Lapham 1989 Survey (N891326)
 Found C.I. in centerline Airport Rd
 N32E 34.01 Power Pole
 N50E 60.18 12" Red Pine
 S08W 38.20 4" Oak
 East 12.51 Capped Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner. Two 1/2" irons found in centerline of road 12.48' apart. GLO falling is 19 lk (12.55'). Westerly iron is being used as G-1. Easterly iron is being used and accepted as G-13, T22N, R2E and has a concrete monument placed 33' North of it. All 1989 Lapham witnesses are in place and corner matches GLO falling.

Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap Marked "27595 1997"
 N32E 34.02 Power Pole
 N50E 59.84 Twin 14" Pine (Spike in S face)
 S13W 38.19 4" Oak
 East 12.48 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap
 N28E 35.65 4" diameter Concrete Monument with Ledy cap
 S61E 94.63 8" Oak

Approved by Peer Review

11-20-97 DATE JAR INITIALS

Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/29/97

