

**SURVEY & REMONUMENTATION**

**MAR 19 1998**

**OGEMAW COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ogemaw  
(County)

Located In: Corner Code #

- |                                    |   |     |   |    |     |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey              | T | 21N | R | 2E | L-1 |
|                                    | T |     | R |    |     |
|                                    | T |     | R |    |     |
|                                    | T |     | R |    |     |
| 2. Property Controlling in Section | S |     | T | R  |     |
|                                    | S |     | T | R  |     |
| 3. Miscellaneous Property in Sec.  | S |     | T | R  |     |
|                                    | S |     | T | R  |     |

**LIBER 3 PAGE 120**  
STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

26 Dec 1997 2:46:29 PM

WANDA MUZIK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Timothy L. Lapham, in a field survey on November 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
GLO not set  
C.P.Co 1968 +- set  
12" Oak SW 41.22  
8" Oak NW 85.79  
6" Oak NNW 76.39

LCRC T. Lapham 9/1988 (L2, P18)  
Found 1/2" iron, wire fence E, Tree line S  
West 5.52 12" Post  
West 25.04 T bar and fence  
S85E 21.50 12" Oak  
S30E 50.30 8" Oak

J. Richardson 9/1970 not set  
Line established as straight between I-13 and M-13 of T22N, R2E

Survey D. Ledy 2/1990 (L4, P360-72)  
Referenced as T iron 5.94 West of L-13, 22N, 2E in witnesses for L-13

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
This corner was not set in the GLO survey.

Consumer's Power 1968 survey was reestablished and the corner set in that survey was found. Conversations with Consumer's personnel indicated that they had no records of why the corner was set at that location. Field notes did not indicate any evidence, GLO or other, found. In 1970 Richardson worked in Section 2, T21N, R2E and reestablished the South line of Sections 35 and 36 (North line Sections 1 and 2, T21N, R2E) as a straight line. No GLO evidence was found along this line of corners and stream calls were inconclusive. Subsequent surveys in Section 36 have used the Consumer's L-13 corner. Consumers, Richardson and all other surveys found use the same M-13 position. The Richardson survey was used for subsequent surveys in Section 2 with corners I-1, I-2, J-1 & K-2, T21N, R2E accepted from his survey. 3 different positions for the K-1 & K-13 corners have been used. (SEE BACK OF FORM)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

Set 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1997"  
N40E 83.16 14" Oak  
S85E 56.80 16" Oak  
S48E 62.32 10" Oak  
S16W 145.86 Power pole  
East 5.94 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap (L-13, T22N, R2E)

Approved by Peer Review

11/20/97 [Signature] JSL  
DATE INITIALS

Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/24/97

