

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

| For Corners In: Ogemaw (County) | Located In | Corner Code # |
|---|--|----------------|
| 1. Public Land Survey | T 21N R 2E T _____ R _____ | D-6 _____ |
| 2. Property Controlling in Section | S 17 T 21N R 2E S _____ T _____ R _____ | 8 _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ S _____ T _____ R _____ | _____ _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on January, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|----|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | • | • | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

8- This corner position was not established during the original government survey.

D-6 This corner position was not established during the original government survey.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

8- Found 3/4" rerod

D-6 Set 5/8" X 32" rerod with P.S. cap #33981 at the intersection of the North- South and East-West one quarter lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8- 3/4" rerod

| | | | |
|------|----------------|-------|--------|
| Wit: | 6" White Birch | N22°E | 60.53' |
| | 3" Ash | S39°E | 35.62' |
| | 4" Ash | N67°W | 72.29' |
| | 3" Elm | S05°W | 41.05' |
| | Carsonite post | North | 1± |

D-6 5/8" X 32" Rerod

| | | | |
|------|-------------------|-------|--------|
| Wit: | 18" Maple | S81°W | 9.20' |
| | 4"-6" Twin Maple | N23°W | 21.06' |
| | 13" Triple Maple | N65°E | 31.21' |
| | 3" Maple | S47°E | 32.66' |
| | Fence corner-wire | N01°W | 68' |
| | Carsonite post | North | 1± |

Signed by: Carl T. Kiiskila
Surveyor's Michigan License No.: 33981

Date: 4/4/00

