

**SURVEY & REMONUMENTATION**

JUN 02 1994

**OGEMAW COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
 OGEMAW COUNTY, MI.

LABER 2 PAGE 228

93 DEC 29 PM 2:59

*Wanda Muzik*  
 REGISTER OF DEEDS  
 OGEMAW COUNTY

For corners in

| OGEMAW<br>(County)                    | Located In:              | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey                 | T <u>21N</u> R <u>3E</u> | <u>M-1</u>    |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**TIMOTHY L. LAPHAM** in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-1: 1838 L. CLASON; POST; TAMARACK 12" N67-1/2W 85LK; S. MAPLE 16" S49W 164 LK; B. OAK 14" N52-1/2E 64 LK; S. MAPLE 10" S53E 60 LK  
 8/13/1971 CALDWELL SURVEY 1-76; DISTANCE NORTH  
 8/1971 CALDWELL LCRC 1-19; CORNER AND WITNESSES  
 1978+/- COUNTY ROAD PLANS; CORNER AND WITNESSES  
 3/3/1989 LEDY LCRC 2-85; RESET CORNER AND WITNESSES

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-1: FOUND RAILROAD SPIKE PER 1989 LCRC FOUND RECORD WITNESSES:  
 NE 101.4' 6" ASH  
 NNW 139.25' PK IN POWER POLE  
 ESE 108.67' SPIKE IN OAK  
 DISTANCE TO NORTH MATCHES 1971 SURVEY

THIS CORNER ESTABLISHED IN OGEMAW COUNTY REMONUMENTATION PROGRAM.  
 SEE DOSSIER FOR DETAILED REPORT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-1: SET 5/8"X36" REROD WITH 3" OGEMAW COUNTY MONUMENT CAP IN MON. BOX  
 AZ 32° 101.43' SPIKE IN SE FACE 8" ASH  
 AZ 343° 139.28' PK NAIL IN NE FACE UTILITY POLE  
 AZ 101° 108.69' SPIKE IN S FACE 13" TWIN OAK  
 AZ 50° 50.90' SPIKE IN SE FACE UTILITY POLE  
 AZ 45° 47.29' CAPPED IRON (LEDY)  
 AZ 136° 46.79' CAPPED IRON (LAPHAM)  
 AZ 230° 58.98' SPIKE IN SE FACE UTILITY POLE



Signed by *[Signature]*

Date 12/28/93

Surveyor's Michigan License No. 27595