

**SURVEY & REMONUMENTATION**

JUN 02 1994

**OGEMAW COUNTY REMONUMENTATION**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED  
 OGEMAW COUNTY, MI.

LIBER 2 PAGE 230  
 93 DEC 29 PM 3:04

*Wanda Mujik*  
 REGISTER OF DEEDS  
 OGEMAW COUNTY

For corners in

OGEMAW (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21NR</u> <u>3E</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, TIMOTHY L. LAPHAM, in a field survey on December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**


M-3: 1837, CLASON, POST, WHITE PINE 17" S52W 41LKS; WHITE PINE 20" N23W 54LKS; 1943, G.SHADKO, SURVEY, CORNER MATERIAL, NO WITNESSES; 2/27/1974, N.CALDWELL, LCRC 1-55, COR MAT, 3 WITS; 1/6/1975, K.OSTLING, SURVEY, COR MAT, NO WITS;

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-3: NO GLO EVIDENCE FOUND. NO CORNER FOUND DUE TO RECENT ROAD CONSTRUCTION. RESET CORNER FROM WITNESSES.  
 N26W 36.32' 14" RED OAK  
 N54E 51.97' 8" MAPLE  
 S21W 43.62' 14" RED OAK  
 ACCEPTED REESTABLISHED CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER.  
 THIS CORNER ESTABLISHED IN OGEMAW COUNTY REMONUMENTATION PROGRAM.  
 SEE DOSSIER FOR DETAILED REPORT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-3: SET 5/8" X 36" REROD WITH 3" OGEMAW COUNTY MONUMENT CAP  
 AZ 331° 36.71' SPIKE SW FACE 16" OAK  
 AZ 48° 51.94' SPIKE NW FACE 11" OAK  
 AZ 196° 44.16' SPIKE SE FACE 15" OAK  
 AZ 164° 50.87' SPIKE SW FACE 12" TWIN BIRCH  
 AZ 90° +/- 115.5 +/- INTERSECTION CENTER LINE OF ROADS



Signed by *[Signature]*

Date 12/28/93

Surveyor's Michigan License No. 27595