

# SURVEY & REMONUMENTATION

JUN 02 1994

COMMISSION

## OGEMAW COUNTY REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
OGEMAW COUNTY, MI.  
LIBER 2 PAGE 216

93 DEC 29 PH 2:56

*Wanda Muzik*  
REGISTER OF DEEDS  
OGEMAW COUNTY

Register of Deeds Stamp & File Number

For corners in  
OGEMAW  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T _____ R _____	_____
	T <u>21N</u> R <u>3E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, TIMOTHY L. LAPHAM, in a field survey on December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-6: 1838 CLASON; POST; W. PINE 8" S62W 43 LKS; S. MAPLE 9" N56W 39 LKS  
12/19/1974 N. CALDWELL; LCRC 1-155; 1" PIPE IN LINE WITH FENCE EAST  
12/23/1974 N. CALDWELL; NO WITNESSES  
5/23/1989 T. LAPHAM; UTILIZED IN ESTABLISHING CENTER OF SECTION 13, NO WITNESSES;  
DISTANCES N 2616.65, S 2620.09 TO RICHARDSON CORNER 2633 +/- TO HENNING CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6: FOUND 1/2" REROD OVER LARGE METAL OBJECT 3' +/- DEEP IN LINE WITH FENCE TO EAST; MATCHED DISTANCES IN 12/23/1974 AND 5/23/1989 SURVEYS  
THIS CORNER ESTABLISHED IN OGEMAW COUNTY REMONUMENTATION PROGRAM.  
SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6: SET 5/8"X36" REROD WITH 3" OGEMAW CO. MONUMENT CAP IN MON. BOX  
AZ 92° 52.23' SPIKE IN S FACE UTILITY POLE  
AZ 56° 38.12' SPIKE IN NW FACE SQUARE FENCE POST  
AZ 290° 53.89' SPIKE IN SW FACE UTILITY POLE  
AZ 210° 80.98' SPIKE IN NW FACE UTILITY POLE



Signed by *T. Lapham* Date 12/28/93  
Surveyor's Michigan License No. 27595