

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OGEMAW (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 3E	M-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 3 PAGE 36

STATE OF MICHIGAN
 OGEMAW COUNTY
 RECORDED

28 DEC 95 3:23 P.M.

WANDA MUZIK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, TIMOTHY L. LAPHAM, in a field survey on December, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-7: GLO 1837 CLASON; TAM. 12", S7W 29L; W. BIRCH 11", NSW 80 L; SUR. 1963 HENNING, 1/2" BAR SET, NOT INTENDED TO DEFINE N-S POSITION; SUR. RICHARDSON, CIRCA 65, ESTAB. CORNER 13'+/- N. OF HENNING BAR; SUR. 9/22/71 DeLAMATER (1-19) NO WITS; SUR. 6/7/71 CALDWELL (1-73) NO WITS; SUR. 4/12/72 CAMPBELL (1-112) NO WITS; SUR. 7/24/72 MCGINNIS (1-127) NO WITS; SUR. 7/31/72 MCGINNIS (1-130) NO WITS; SUR. 12/23/74 CALDWELL (1-549) NO WITS; SUR. 5/29/75 CAMPBELL (1-579) NO WITS; SUR. 3/10/76 CAMPBELL (2-65) 3 WITS; SUR. 9/28/76 CAMPBELL (2-159) 3 WITS; LCRC 6/17/77 CALDWELL (1-155) 3/8" BAR 4 WITS; 78 CO RD PLANS, 1/2" BAR 1 WIT; SUR. 9/11/81 HIGGINS NOT RECORDED, RESET 1/2" BAR; LCRC 2/15/82 HIGGINS (1-247) 1/2" BAR 4 WITS; LCRC 5/16/88 LEDY (1-375,6) 1/2" BAR 4 WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7: NO GLO EVIDENCE FOUND. FOUND HENNING AND RICHARDSON IRONS. ALL SUBSEQUENT SURVEYS USE ONE OF THEM WITH GENERALLY T21NR4E BASED ON HENNING CORNER AND T21NR3E BASED ON RICHARDSON CORNER. HOWEVER, HENNING STATED THAT HE DID NOT ATTEMPT TO FIX N-S POSITION OF CORNER. HTHEREFORE REJECTED ALL SURVEYS BASED ON HENNING IRON AND ACCEPTED RICHARDSON IRON AS BEST EVIDENCE OR CORECTLY ESTABLISHED CORNER POSITION. SEE DOSIER FOR ADDITIONAL INFORMATION.

APPROVED BY
 PEER REVIEW
 2/15/1995
 DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

M-7: SET 5/8"x36" REROD WITH 3" ALUMINUM REMON CAP IN MON. BOX
 S40E 92.78 UTILITY POLE W/ TAG
 S32E 82.81 FACE OF CORNER POST
 N86E 57.08 NORTH INVERT OF 24" CMP
 S79E 49.36 STOP SIGN POST
 S77W 46.94 STOP SIGN POST
 S66W 58.62 CORNER POST W/ TAG
 S07E 13.21 1/2" IRON IN MON BOX

Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 2/28/95

