

**SURVEY & REMONUMENTATION**

JUN 02 1994

COMMISSION

**OGEMAW COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OGEMAW (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>3E</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED  
OGEMAW COUNTY, MI.  
LIBER **2** PAGE **236**  
93 DEC 29 PM 3:05  
*Wanda Mizik*  
REGISTER OF DEEDS  
OGEMAW COUNTY

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, TIMOTHY L. LAPHAM, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-11: 1838 L. CLASON; POST; W. PINE 15" S10W 22 LK; W. PINE 28" N79W 20 LK  
1985+/- R. MILLER; SURVEY USED CORNER  
8/27/1987 R. MILLER; SURVEY REFERENCED CORNER WITH DISTANCE NORTH

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-11: FOUND 1/2"X36" REROD OVER BENT 1/2" REROD 2.5'+/- DEEP, 1'+/- EAST OF CENTERLINE OF PAVEMENT AT FENCE LINE WEST; CORNER FALLS AT 1/3 OF THE DISTANCE BETWEEN CORNERS M-10 AND M-13  
ACCEPTED FOUND CORNER AS BEST EVIDENCE OF ORIGINAL CORNER POSITION.  
THIS CORNER ESTABLISHED IN OGEMAW COUNTY REMONUMENTATION PROGRAM.  
SEE DOSSIER FOR DETAILED REPORT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-11: SET 5/8"X36" REROD WITH 3" OGEMAW COUNTY MONUMENTATION CAP IN MONUMENT BOX;  
AZ 234° 53.56' NAIL IN SE FACE 23" WHITE PINE, BLAZED  
AZ 266° 40.7' FACE OF SQUARE CONCRETE POST  
AZ 290° 69.12' NAIL IN S FACE 25" WHITE PINE, BLAZED  
AZ 66° 135.15' NW CORNER OF GARAGE  
AZ 120° 83.91' NAIL IN SW FACE 20" WHITE PINE



Signed by *Timothy L. Lapham*

Date 12/28/93

Surveyor's Michigan License No. 27595