

SURVEY & REMONUMENTATION

JUN 02 1994

COMMISSION

OGEMAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>OGEMAW</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>21N</u> R <u>3E</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
OGEMAW COUNTY, MICH.
LIBER 2 PAGE 237

93 DEC 29 PM 3:05

Wanda Mizik
REGISTER OF DEEDS
OGEMAW COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, TIMOTHY L. LAPHAM, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12: 1838 L. CLASON; POST; W. PINE 20" S39W 27 LK; W. PINE 20" N79W 20 LK 1985+/- R. MILLER; CORNER REFERENCED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12: FOUND 1/2"X18" REROD WITH OBLITERATED PS NUMBER ON CAP; IN CENTERLINE OF PAVEMENT; 300'+/- SOUTH OF SOUTH EDGE OF MARSHY AREA (GLO CALLS FOR 264'); MIDWAY BETWEEN CORNERS M-11 AND M-13 WITH 0°05' DEFLECTION AT CORNER

THIS CORNER ESTABLISHED IN OGEMAW COUNTY REMONUMENTATION PROGRAM.
SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12: SET 5/8"X36" REROD WITH 3" OGEMAW COUNTY MONUMENT CAP IN MON. BOX.
AZ 285° 42.97' NAIL IN S FACE 9" RED PINE, BLAZED
AZ 265° 40.80' NAIL IN N FACE 14" RED PINE, BLAZED
AZ 154° 79.17' NAIL IN NE FACE POWER POLE
AZ 102° 64.69' NAIL IN N FACE 4" SCOTCH PINE, BLAZED



Signed by *[Signature]*

Date 12/28/93

Surveyor's Michigan License No. 27595