

**SURVEY &  
REMONUMENTATION**

MAY 28 1987

OGEMAW COUNTY REMONUMENTATION

LIBER 113 PAGE 100

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 4E	C - 1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

30 DEC 96 4:33 P.M.

WANDA MUZIK  
Register of Deeds, Stamp & File Number  
REGISTER OF DEEDS

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Timothy L. Lapham, in a field survey on December, 19 86 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO B.F.Hall, 1848	Found 1-1/4" pipe in old road
Set post 85 links West of C13 T22N R4E	8" Elm S60W 37.2'
W. Pine 4" S06W 20 links	9" Tw. Elm N52-1/2W 19.55'
W. Pine 4" S06E 17 links	7" Elm S04W 12.47'
Survey Henning 8/21/41	LCRC Ledy 6/16/89 (Rec L2, P85-86)
No corner material	Found 1-1/2" pipe
East 43.8' iron pipe	East 42.91' 1-1/2" pipe
Survey Henning 9/51	SE 96.21' Spike in 20" Willow
1-1/2" pipe	SSE 87.17' Spike in 16" Willow
No wits	WSW 56.60' Spike in 6" Ash
Unrecorded Survey, Richardson	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of GLO corner found. Found 1-1/2" pipe and Ledy witness. Accepted found pipe as best evidence of the position of the original corner.

APPROVED BY  
PEER REVIEW  
12-18-96 TW  
DATE P.A. 345 of 1990

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8"X36" re-rod with 2-1/4" Aluminum cap Marked "1996 27595"  
From Which:  
N70W 63.97' 10" Ash  
S86E 42.91' 5/8" capped rerod C-13 T22N R4E  
S75E 87.32' 26" Willow  
S46E 96.12' 36" Willow



Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/27/96