

SURVEY &
REMONUMENTATION

MAY 28 1997

OGEAW COUNTY REMONUMENTATION

LIBER 12.3 PAGE 103

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 4E	F - 1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
OGEAW COUNTY
RECORDED
30 DEC 96 4:34 P.M.
WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Timothy L. Lapham, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Not Set by GLO
- Unrecorded Survey, Lapham, 10/15/87
- Set Capped Iron
- N45W 55.00' Fence Corner post
- N40E 58.84' Power Pole
- S80E 75.43' Tree
- East 41.78' 1/4"x1" Bar F13 T22N R4E
- Unrecorded Survey, Lapham, 12/98
- Found Capped Iron
- Same Wits as Above

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in accord with previous Lapham surveys. Corner was set midway between E-13 and F-13 of T22N R4E and on line between E-1 and G-1. Accepted found iron as a careful establishment according to the rules set forth by the BLM. See dossier for additional information.

APPROVED BY
PEER REVIEW
12-18-96 JL
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"x3/8" re-rod with 2-1/4" Aluminum cap Marked "1986 27595"
- From Which:
- N58E 52.15' Fence Corner Post
- S04W 33.00' 1/2" capped iron
- S74W 75.26' 8" Ash
- N25W 58.93' Utility Pole
- East 41.74' 5/8" capped iron F-13 T22N R4E
- South 1' Centerline Hardwood Heights Road



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/96