

**SURVEY &  
REMONUMENTATION**

**SEP 28 1998**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ogemaw SECTION \_\_\_\_\_  
(County)

Located in:

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>22N</u> R <u>1E</u> | <u>A-2</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on 4-29, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-2 GLO - 1838 L. Clason, D.S.  
Mon. - Post  
8" Spruce Pine S54°W 22 lks  
8" Spruce Pine N41°30'W 18 lks

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Set Single Proportionate between M-1, and M-3 of T22N-R1W. Position falls in North-South fence and tree line to the West. No Corner evidence found. GLO witness trees destroyed by North South trail. Accepted as a reestablishment of the position of the position of the Original Corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon - Set Standard Roscommon County Monument.  
Set nail in the SE. side of a 22" Red Pine S54°W 56.45'  
Set Nail in the W. side of a 10" Jack Pine N01°W 52.38'  
Set Nail in the SE. side of a 8" Red Pine S38°W 74.80'  
Set Nail in the N. side of a 12" Red Pine S88°E 64.54'

**LIBER 3 PAGE 171**  
STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED  
7/14/1998 9:26:45 AM  
WANDA MUZIK  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Approved by Peer Review  
6/4/1998 JM  
DATE INITIALS

Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600



Date June 4th 1998