

SURVEY &
REMONUMENTATION

SEP 28 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw
(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>22N</u> R <u>1E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **3** PAGE **174**
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

7/14/1998 9:26:45 AM

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on 4-23, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>A-5 GLO - 1837 John Brink, D.S. Mon. - Post 13" White Oak S59°W 48 lks. 15" Y. Pine N23°W 109 lks. GLO - 1846 B.F. Hall, D.S. Mon - Post Wit: 8" W. Oak N30°E 14 lks 10" W. Pine S73°E 48 lks L. 2, Pg. 155 Mon. - 1 1/4" Buggy Axle In N-S fence line. Near CenterLine Firelane West. 10" N. Pine S31°W 54.94' 15" Oak N81°W 58.74' 16" Oak N25°W 61.16' Fence Post North 3.83'</p>	<p>L. 1, Pg. 119 (Norman C. Caldwell, P.S. # 12018 4-18-1966) Mon. - 1 1/4" Buggy Axle In N-S fence line. Near CenterLine Firelane West. 10" N. Pine S31°W 54.94' 15" Oak N81°W 58.74' 16" Oak N25°W 61.16' Fence Post North 3.83'</p>
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1 1/4" Axle Shaft 1.0' West of North-South fence, and in centerline of old North-South road corridor. Found Oak stumps of record, they were rotten. Found nail with MDOT tag in the SE. side of a 16" Red pine S33°W 54.84'. Found nail with MDOT tag in the S. side of a 6" Oak N60°E 43.62'. Accepted as the best available evidence of the position of the Original Government Corner. Replace axle shaft with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon.- Standard Roscommon County Monument.
Set nail in the E. side of a 4" Cherry South 2.88'
Set nail in the NE. side of a 4" Oak in a clump N57°W 28.75'
Found nail with MDOT tag in the SE. side of a 16" Red pine S33°W 54.84'
Found nail with MDOT tag in the S. side of a 6" Oak N60°E 43.62'

Approved by Peer Review

6/2/1998 WU
DATE INITIALS

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600



Date June 4th 1998