

SURVEY &
REMONUMENTATION

SEP 28 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

Ogemaw
(County)

Located In:

Corner Code #

LIBER 3 PAGE 176

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

7/14/1998 9:26:45 AM

WANDA HUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>1E</u> | <u>A-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on 3-26, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>A-7 GLO - 1837 John Brink, D.S.
Mon. - Post
16" Yellow Pine N66°W 8 lks.
14" Yellow Pine S13 1/2°W 10 lks.
GLO - 1846 B.F. Hall, D.S.
Mon - Post
Wit: 3" Aspen N44°E 17 lks.
5" Aspen S77°E 25 lks.
J. Richardson (RLS)
Mon.- Found two Gov. Bts. & stains with charcoal set 1/2"x36" iron & wood marker at corner
16" B. Oak S48 1/2°W 54.32'
9" B. Oak S42°E 21.69'</p> | <p>L. 1, Pg. 35 (Larry L. Cavanagh P.S. #17814 April 3, 1973)
Mon. - Found 1/2" bar in fence.
17" Oak S61°W 55.01' (NBT)
9" Oak S37°E 22.31' (NBT)
10" Oak N21°W 69.60'</p> | <p>L. 1, Pg. 120 (Norman C. Caldwell, P.S. #12018 April 19, 1966)
Mon - Fd. 1/2" Bar set by J. Richardson, RLS corner is in fence corner North & East.
17" Oak S61°W 55.01' (NBT)
9" Oak S37°E 22.31' (NBT)
10" Oak N21°W 69.60'</p> |
| <p>Mon.- Found two Gov. Bts. & stains with charcoal set 1/2"x36" iron & wood marker at corner
16" B. Oak S48 1/2°W 54.32'
9" B. Oak S42°E 21.69'</p> | <p>L. 2, Pg. 156
Mon.- Found 1/2" bar
17" Oak S61°W 55.01'
9" Oak S37°E 22.31'
6" W. Oak N25°E 51.7'
10" Oak N21°W 69.60'</p> | <p>L. 3, Pg. 357 (R. L. Higgins, P.S. 21570 April 27, 1982)
Mon - Not given.
Wit: None given</p> |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in fence corner. Fence runs to the East and North. Corner is in the centerline of East-West & North-South Firelane Roads. Found nail in the NE side of a 10' Oak N52°W 44.27; Found nail in the N. side of a 14" Oak S42°E 22.21; Found Nail in the West side of a 16" Oak S11°W 36.93. Accepted as a perpetuation of the Original Government Corner. Replaced 1/2" iron with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon.- Standard Roscommon County Monument.
Found nail in the NE. side of a 10" Oak N52°W 44.27'
Found nail in the N. side of a 14" Oak S42°E 22.21'
Found nail in the W. side of a 16" Oak S11°W 36.93'
Set nail in the SE. side of a 20" Oak S58°W 54.84'

Approved by Peer Review
6/2/1998 JA
DATE INITIALS

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600



Date June 27 1998