

SURVEY & REMONUMENTATION

SEP 28 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Ogemaw
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>1E</u> | <u>A-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 3 PAGE 178
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

7/14/1998 9:26:45 AM

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on 3-26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|--|
| <p>A-9 GLO - 1837 J. Brink, D.S.
Mon. - Post
16" Yellow Pine N25°W 53 lks. Mon - 1/2" bar in Center of Roads set
14" Yellow Pine S75°W 83 lks.
GLO - 1846 B. F. Hall, D.S.
Mon - Post
Wit: 36" Y. Pine N17°E 72 lks.
36" W. Pine S79 1/2°E 73 lks.
M. Schaaf, RLS
Found or established, & replaced
George D. Henning RLS# 2240
July 13, 1976
Mon.- 1 1/2" bar in center of roads
set from orig. U.S. witnesses
5" W. Oak N45°W 46.4'
6" B. Oak N38°E 47.9'
8" R. Oak S47°E 64.8'</p> | <p>George D. Henning RLS #2240
May 1967
from Orig. U.S. Witnesses.
5" W. Oak N45°W 46.4'
6" B. Oak N38°E 47.9'
8" R. Oak S47°E 64.8'</p> <p>Robert Higgins, P.S. #21570 Nov. 10, 1978
Mon.- Found 1/2" iron
5" W. Oak N45°W 46.4'
6" B. Oak N38°E 47.9'
8" R. Oak S47°E 64.8'</p> | <p>L. 2, Pg. 185 (Timothy L. Lapham
P.S. #27595 July, 29 1992 & Mar. 16, 1997)
Mon. - Found 1/2" iron of record
12" Oak S40°E 25.73'
6" Oak S80°E 46.33'
14" Oak N10°W 34.00'
14" Oak N75°W 26.47'</p> <p>L. 6, Pg. 9 (Duane F. Ledy P.S. #21575 12-1-94)
Mon. - Found 1/2" Rod @ Int. of 2-Track Rds.
Spikes in: 14" Oak N55°E 79.57'
Stump S80°E 46.29'
12" Oak North 34.19'
18" Oak N45°W 26.72'</p> |
|--|---|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" Iron in centerline of trail roads to the East, West, South, and S72°W. Found nail in the W. side of a 12" Oak N05°W 33.97'. Found nail in the N. side of an 18" Oak N70°E 79.63'. Found nail in the S. side of an 8" Oak S76°E 46.33'. Found nail in the NE. side of a 16" Oak N68°W 26.49'. Accepted as a perpetuation of the Original Government Corner. Replaced with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon.- Standard Roscommon County Monument.

- Wit: Found nail in the W. side of a 12" Oak N05°W 33.97'
Found nail in the N. side of a 18" Oak N70°E 79.63'
Found nail in the S. side of a 8" Oak S76°E 46.33'
Found nail in the NE. side of a 16" Oak N68°W 26.49'
Set Carsonite Post S43°W 20±

Approved by Peer Review

6/21/98 JM
DATE INITIALS

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600



Date June 27 1998