

APR 08 1999

Ogemaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R01E	G-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 3 PAGE 201

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

23 DEC 1998 3:46:07 PM

WANDA MUZIK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Timothy L Lapham, in a field survey on December, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

G-10: GLO 6/21/1846 B.F. Hall set post  
 Maple 4" S31W 11lk  
 Beech 10" N63E 30 lk  
 Survey 1-496 7/23/1974 L. McGinnis set 3/8" iron  
 N60W 32.05 nail in 30" Maple  
 E 19.9 nail in 30" Maple  
 Section break 7/1974 L. McGinnis - same as survey 1-496

Co. road plans T. Lapham fd. 3/8" bar  
 12" Tw. Ash N50W 49.89  
 14" Tw. Ash S38W 97.1  
 26" Maple S20E 79.0 (1)  
 1/2" bar East 33.0

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10: No evidence of GLO corner. Found 3/8" rered 1'+/- East of centerline. Found witness (1), measured 79.48. Accepted found rered as best evidence of correct position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10: Set 5/8"x36" rered with aluminum Ogemaw county remon. cap.  
 Witnesses:  
 N23W 45.63 spike in SW face of 8" twin Beech  
 S40W 64.19 spike in NW face of 10" Poplar  
 S25E 79.48 new spike in SW face of 26" Maple  
 S81E 20.98 nail in N face of 24" Norway Spruce  
 S30E 36.11 nail in SW face of 24" Norway Spruce

Approved by Peer Review

12/15/98 DATE INITIALS



Signed by [Signature]  
Surveyor's Michigan License No. 27395

Date 12/23/98