

APR 08 1999

Ogemaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw
(County)

Located in:

Corner Code #

- 1. Public Land Survey T22N R01E G-12
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

LIBER 3 PAGE 203

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

23 DEC 1998 3:46:35

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-12: GLO 6/21/1946 B.F. Hall set post
Hemlock 20" East 9 lk
Hemlock 6" N80W 36 lk
- Survey 1-498 & 2-98 4/23/1974 L. McGinnis set 3/8" iron
WNW 50.57 nail in 12" Poplar
W 41.76 nail in 16" Poplar (1)
- Section break 1974 L. McGinnis - same as survey 1-498
- Survey 2-100 3/26/1976 L. McGinnis - same as survey 1-498
- LCRC 1-170 3/1977 L. McGinnis - same as survey 1-498
- Survey 2-480 7/20/1978 G.Henning same as survey 1-498

- Survey unrecorded 9/10/1990 T. Lapham same as survey 1-498
- Co. road plans 1997 J.P. May set conc. nail from previous survey
10" R. Pine N63E 69.35 (2)
10" R. Pine S44E 62.51 (3)
UP S18W 107.13 (4)
14" Maple N73W 43.42 (5)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-12: No evidence of GLO corner. Reset from 1997 witnesses, road built up 5'+/-. Found very deteriorated stump of witness (1), measured 42' to centerline of stump. Found witnesses (2) (4) and (5), reset point from these witnesses. Found witness (3), measured 62.61. Accepted reestablished point as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-12: Set 5/8"x36" rerod with aluminum Ogemaw county remon. cap.

- witnesses
- N49E 57.16 spike in W face of 10" R. Pine
- S42E 62.61 spike in NE face of 10" R. Pine
- S28W 107.13 spike in NW face of Power pole
- N68W 43.42 spike in SW face of 14" Maple
- N61E 69.35 spike in SE face of 10" R. Pine

Approved by Peer Review

12/15/98 JAL
DATE INITIALS

Signed by [Signature]

Surveyor's Michigan License No. 27595

Date 12/23/98

