

FEB 24 2000

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R01E	K-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

3006786
Page: 1 of 1
12/27/1999 09:09A
L-3 P-295
Wanda Muzik, Ogemaw Co. Registrar SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on December 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-7: GLO by B.F. Hall, 1848, post N33E 22 6" Beech N55W 10 8" Beech
Survey by D. Ledy, 1985, found 1/2" rod No Witnesses
S64W 73.09 Northeast Cor Trailer
- LCRC by A.V. Courtright, 1973, found 1/2" iron
West 20.57 Fence post East 25.83 Fence post S65E 52.23 12" White Birch
Survey by R. Higgins, 1961, no material
W4133.0 Concrete Monument
Survey by R. Higgins, 1976, found 7/8" bar
Survey by L. Cavanagh, 1974, found 1/2" bar
Survey by R.L. Miller, 1998, found bar S39W 70.54 Southeast Cor of house foundation
S63E 51.42 9" Birch Due East 25.60 Fence Cor Post
- LCRC by J.L. Wilcox, 1966, found 1/2" iron rod
S39W 70.54 Southeast Cor of house foundation
S63E 51.42 9" Birch Due East 25.60 Fence Cor Post
Survey by L. Cavanagh, 1974, found 1/2" bar
East 33.08 Capped Iron
Survey by R. Higgins, 1977, found 7/8" iron No witnesses
Survey by R.L. Miller, 1998, found bar S39W 70.54 Southeast Cor of house foundation
S63E 51.42 9" Birch Due East 25.60 Fence Cor Post
- Survey by D. Ledy, 1984, found 1/2" rod
S39W 70.54 Southeast Cor of house foundation
S63E 51.42 9" Birch Due East 25.60 Fence Cor Post
County Road Plans, 1999, found 1/2" iron bar
N83E 60.93 6" Twin Poplar
S60E 51.68 12" Birch
S20W 102.84 Utility Pole
- Survey by T. Lapham, 1985, found 1/2" iron
S88E 26.51 Fence Corner
S39E 52.19 4" Ash
S17W 102.20 Utility Pole
S63W 73.15 Northeast Cor Mobile Home
Survey by J. May, 1999, found 1/2" iron
N89E 61.22 5" Twin Poplar
S57E 51.86 9" Birch
S37E 52.22 7" Elm
S24W 102.06 Utility Pole
- Survey by D. Ledy, 1989, found 1/2" rod
S39W 70.54 Southeast Cor of house foundation
S63E 51.42 9" Birch Due East 25.60 Fence Cor Post
Survey by J. Richardson, 1962, Found bent pipe set 1/2" bar
S52W 58.07 NE Cor House
S62E 47.56 8" Elm
S38E 70.79 14" Elm

Approved by Peer Review
12-16-99
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7: No GLO survey evidence found. Found capped iron reset from 1999 road plan witnesses. Found 1 - 1996 witness and 1 - 1973 witness that match re-established position. Distance to K-8 matches 1966 through 1999 records except 1976 survey 2-109. No evidence of corner at 1976 distance. Accepted found iron as best evidence of correct corner position.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7: Set 5/8"x3/8" rerod w/aluminum remon cap
N83E 60.93 6" Twin Poplar
S60E 51.68 12" Birch
S20W 102.84 Utility Pole
S64W 73.09 NE Cor Trailer

S32E 52.25 6" Ash

signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/23/1999

