

FEB 24 2000

SECTION

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R01E	K-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	



3006803
Page: 1 of 1
12/27/1999 09:09A
L-4 P-12
Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
K-8: GLO by B.F. Hall, 1846, Aspen 4"

Survey by F. King, 1987, Found 3/4" pipe
No witnesses

LCRC by J.L. Wilcox, 1966, Set 3/4" pipe
N34W 39.03 5" Pine
Due West 29.09 3/4" Pipe
S82W 78.28 8" Pine
N55W 61.85 4" Maple

Survey by T. Lapham, 1997, Found 1 1/4" pipe
S52W 38.31 12" White Pine
N54W 39.20 10" White Pine
S89E 62.36 10" Maple
South 283+- Centerline Railroad Tracks

County Road Plans, 1999, Found 1 1/4" pipe
N40E 84.90 Utility Pole
S85E 62.43 14" Twin Maple
S24W 96.60 26" White Pine
N87W 83.05 14" White Pine

Survey by T. Lapham, 1995, Found 1 1/4" pipe
S52W 38.31 12" White Pine
N54W 39.20 10" White Pine
S89E 62.36 10" Maple
South 283+- Centerline Railroad Tracks

Survey by R. Higgins, 1976, Found pipe
No witnesses

Survey by R. Higgins, 1974, Found 3/4" pipe
No witnesses

Approved by Peer Review

12-16-99
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-8: No evidence found of GLO survey or 1966 LCRC. Found capped iron reset from 1999 road plans. Distance to K-7 and K-9 substantially match 1966 dimensions through 1999 road plans except for 1976 survey 2-109 distance to K-7. No additional Irons found at either K-7 or K-8 to verify 1976 survey. Accepted re-established position as best evidence of corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-8: Set 5/8"x36" rerod w/aluminum cap

N40E 84.90 Utility Pole
S85E 62.43 14" Twin Maple
S24W 96.60 26" White Pine
N87W 83.05 14" White Pine
South 284+- Centerline Railroad Tracks

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/23/1999