

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

OGEMAW COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3 PAGE 79

For corners in

Ogemaw	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 22N R 1E	M - 12
	T 22N R 2E	A - 12
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED  
30 DEC 96 4:29 P.M.  
WANDA MUZIK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Timothy L. Lapham in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- |   |                                     |
|---|-------------------------------------|
| Note: Corner Common to A-12 T22N R2E              | No corner material or witnesses     |
| GLO, L. Clason, 1838                              | LCRC Higgins 2/15/82 (Rec L1, P257) |
| Beech 10" S43W 13 links                           | 1/2" Steel bar                      |
| Red Oak 16" N35W 33 links                         | N45E 48.59' 28" Twin Basswood       |
| LCRC Wilcox, 4/68 (rec 2/77 L1, P143)             | S80E 41.33' 30" Twin Ash            |
| 1/2" Bar  | S30E 88.42' 23" Elm                 |
| N45E 48.59' 28" Basswood                          | S80W 38.17' Power Pole              |
| S80E 41.33' 30" Twin Ash                          | MDOT ROW map, no material or wits;  |
| S30E 88.42' 23" Elm                               | Survey, Henning Section Subdivision |
| S80W 38.17' P.Pole                                | No material or witnesses            |
| Survey, Higgins, 9/30/80 (Rec L3, P178, L3, P186) |                                     |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
No evidence of GLO found. Corner apparently torn out during road construction. Set monument at GLO proportionate & M-DOT proportionate distance on Township line. See dossier for additional information.

APPROVED BY  
PEER REVIEW  
12-18-96 JW  
DATE P.A. 345 of 1990

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set 5/8" X 3/8" rerod with 2-1/4" Aluminum cap marked "1996 27595"
- From Which:
- N42E 122.87' Utility Pole
- N85E 107.24' 4" Ash
- S18E 28.77' Guard rail post
- N82W 27.29' Guard rail post
- Monument located in median of I-75, 50' North of centerline of Southbound lanes.



Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/27/96