

MAY 28 1997

COMMISSION

OGEMAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 22N R 1E	M - 3
	T 22N R 2E	A - 3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

30 DEC 96 4:27 P.M.

WANDA NUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Timothy L. Lapham, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Note: Corner Common to A-3 T22N R2E
GLO L.Clason 1838
Set post
Y. Pine 18 S66W 21 links
W. Pine 30 N41W 30 links
GLO B.F.Hall 1846
Found post
W. Pine 22 N73-1/2E 83 links
Survey, Richardson, 874
No material or witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO found. Found 2" pipe at intersection of trails and four apparent witness trees. Accepted as best evidence of the position of the original corner. See dossier for additional information.

APPROVED BY
PEER REVIEW
12-18-96
DATE 7/2 P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X 36" rerod with 2-1/4" Aluminum cap marked "1996 27595"
From Which:
N50E 26.79' 5" Maple
S40W 34.52' 14" W. Oak
S64W 21.83' 8" Maple
N30W 33.52' 8" Maple
Monument located 5' South of centerline trail East-West and 3' East of centerline trail North-South



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/96