

MAY 28 1997

COMMISSION

OGEMAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 2E	B . 7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

30 DEC 96 4:31 P.M.

WANDA NUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	l
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Timothy L. Lapham, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Hall 1845	3 wits;
8" Aspen for post	Survey, Lapham 10/96, (Rec L5, P350)
Survey, Higgins 8/78 (Rec L2, P531)	No corner material or wits;
Set 1/2" X 18" bar	
LCRC, Ledy 11/83 (Rec L1, P298)	
Set 1/2" iron bar with cap #21575	
4 wits;	
Survey, Ledy 8/84 (Rec L3, P548)	
Found 1/2" bar at fence	
LCRC, Lapham, 7/86 (Rec L1, P349)	
Found 1/2" RLS capped iron	


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner found. Found 1/2" capped iron in accord with recorded LCRCs. Accepted found corner as best evidence of the position of the original corner. See dossier for additional information.

APPROVED BY
PEER REVIEW
12-18-96
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X 36" rerod with 2-1/4" Aluminum cap marked "1996 27595"
From Which:
N81E 38.31' 8" Cedar
S22E 30.40' 6" Poplar
S53W 21.85' 10" Poplar
N42W 21.88' 4" Poplar



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/96