

**SURVEY &
REMONUMENTATION**

MAR 19 1998

OGEMAW COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R 2E	B - 13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER 3 PAGE 147

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

26 Dec 1997 2:57:16 PM

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L. Lapham, in a field survey on November 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Clason 1837 set post Y. Birch 16" N56E 36 lk Hd. Maple 9" N70W 37 lk	Ledy 1988 Survey (L4, P228) 19.19' E of N 1/4 corner Sec 6, 21N, 2E
G. Henning 1954 Survey No witnesses - section break	T. Lapham 1996 Survey (N965178c) Found 1" pipe N20W 19.29 16" S. Maple S58W 16.06 8" Basswood N60W 51.28 10" S. Maple
Roser 1965 (MDSH) LCRC (L1, P90) S89°32'06"E 19.19 from N 1/4 corner Sec 6, T21N, R2E	

R. Higgins 1978 Survey (L2, P432)
South line section 31 shown,
no corner shown

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe for corner and pipe with 1/2 union 19.05 West of corner. Both in old E-W fence line. No evidence of GLO corner. Both corners as set in 1965. Found 3 1996 Lapham witnesses. No other evidence of corner position.

Accepted Found corner as best evidence of correct position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remonumentation cap marked "27595 1997"
West 19.05 Aluminum Ogemaw County Monument
N21W 19.29 16" Maple
S61W 16.07 8" Basswood
N61W 51.28 14" Maple
N04E 54.0 centerline of corner steel post, fences N & E

Approved by Peer Review

11-20-97 JLL
DATE INITIALS

Signed by _____
Surveyor's Michigan License No. 27595

Date 12/24/97

