

MAY 28 1997

OGE MAW COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw (County)	Located in:	Corner Code #
1. Public Land Survey	T 22N R 2E	C - 2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
OGE MAW COUNTY
RECORDED

30 DEC 96 4:29 P.M.

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L. Lapham, in a field survey on December, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO, Hall 1845
- Set Post
- W. Oak 3 S52E 10
- Unrecorded Survey, Richardson 8/72
- No corner material or Wits;
- Survey, Higgins, 7/77 (Rec L2, P332)
- Found 1/2" Bar
- Reference spike East 58.56'
- Survey, Higgins, 10/82 (Rec L3, P533)
- Found 1/2" bar
- No wits;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner found. Found 1/2" iron and 1"X2" white hub. Accepted found corner as best evidence of the position of the original corner. See dossier for additional information.

APPROVED BY
PEER REVIEW

12-18-96 JW

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"X3/8" rerod with 2-1/4" Aluminum cap marked "1996 27595"
- From Which:
- N03E 19.62' PK nail in top of Guard Rail Post
- East 22.00' Centerline Fairview Road
- East 3.0' Back of Guard Rail
- S08E 36.77' Nail in End of guard rail post
- S44W 23.96' Utility Post



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/29/96