

MAY 28 1997

COMMISSION

OGEMAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Ogemaw (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED
30 DEC 96 4:30 P.M.
WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Timothy L Lapham, in a field survey on December 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at row 5, column C.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO, Hall 1845
Set post
Beech 12 S57E 14
Hemlock 14 S62W 13
LCRC, Cavanagh, 473 (Rec L1, P37)
Found 1" axie shaft, Placed 1/2"X36" bar
4 wits;
Survey, Cavanagh, 5/74 (Rec L1, P401)
No material or wits;
Survey, Cavanagh, 6/76 (Rec L2, P130)
Found 1/2" steel bar
3 wits;
Survey, King, 3/82 (Rec L5, P181)
Fd. Rec Iron
No wits;
LCRC, Lapham, 3/93 (Rec L2, P201)
1/2" Iron
4 wits;
Survey, Lapham, 10/95
Found capped iron of record

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner found. Found 1/2" iron in accord with Lapham LCRC. Distance North in accord with King and Lapham Surveys. Accepted found corner as best evidence of the position of the original corner. See dossier for additional information.

APPROVED BY
PEER REVIEW
12-18-96
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"X36" rerod with 2-1/4" Aluminum cap marked "1986 27595"
in Monument Box
From Which:
N06E 58.33' 4" Appie
S12E 50.97' NW corner Garage
S61W 92.82' Fence Post
N54W 98.76' Utility pole
Monument located in Centerline Maes road East-West and 40' east of Centerline Fairview road North-South



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/96