

MAY 28 1997

OGEMAW COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 2E	C - 9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED  
30 DEC 96 4:31 P.M.  
WANDA MUZIK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Timothy L. Lapham, in a field survey on December, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |                                        |                                       |
|----------------------------------------|---------------------------------------|
| GLO, Hall 1845                         | No material or Wits;                  |
| 4" Aspen for Post                      | LCRC, Higgins, 10/80 (Rec L1, P219)   |
| Survey, McGinnis, 12/72 (Rec L1, P189) | Found 1/2" bar                        |
| No material or wits;                   | 4 wits;                               |
| Survey, Cavanagh, 12/73 (Rec L1, P335) | Survey, Higgins, 11/80 (Rec L3, P228) |
| No material or wits;                   | No material or Wits;                  |
| Survey, Cavanagh, 2/74 (Rec L1, P377)  | Survey, Lapham, 11/92 (Rec L5, P254)  |
| No material or wits;                   | Found 1/2" Iron                       |
| Survey, Higgins, 8/76 (Rec L2, P114)   | 228' North of M55                     |
| Found 1/2" Bar 229' N of M55           |                                       |
| Survey, Higgin 8/78 (Rec L2, P473)     |                                       |


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner found. Found 1/2" Iron 229' North of M-55. Distance North matches Lapham survey. Accepted found corner as best evidence of the position of the original corner. See dossier for additional information.

APPROVED BY  
PEER REVIEW  
*12-18-96 JL*  
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"x3/8" rod with 2-1/4" Aluminum cap marked "1996 27595"
- In Monument Box
- From Which:
- N36E 43.74' Speed limit Sign
- S12E 95.00' Telephone Ped. Top Center
- S18W 89.64' Utility Pole
- N75W 33.72' 1/2" Iron in asphalt
- Monument located in Centerline Fairview Road North-South and 229' North of Centerline M-55 East-West



Signed by *Timothy L. Lapham*  
Surveyor's Michigan License No. 27595

Date 12/27/96