

**SURVEY &
REMONUMENTATION**

MAR 19 1998

OGEMAW COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Ogemaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>2E</u>	<u>D-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER 3 PAGE 148

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

26 Dec 1997 2:57:37 PM

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L. Lapham, in a field survey on November 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Clason 1837 set post
- B. Ash 7" N40E 24 lk
- Cedar 9" n61W 16 lk
- No closing corner set
- J. Richardson 1960 Survey
- No witnesses - section break
- 1965 Slattery (MDSH) cor records & LCRC (L1P88)
- Found sq. post, set 1" pipe
- S45E 23.47 6" Elm
- N82E 42.10 12" Quad Cedar
- N20E 48.26 11" ELM
- S89°21'24"W 12.87 N 1/4 cor Sec 5
- McGinnis (Edmonds Engineering) 1974 Survey (L1, P415)
- Corner shown, no witnesses

T. Lapham 1989 Survey (L4, P266)
Corner shown, 12.95' E of N 1/4 cor
Sec 5, T21N, R2E

T. Lapham 1996 Survey (N965203)
Corner shown, no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO

Found 1" pipe for corner and T post 12.92' west. West iron approximately in fence N & S. Both irons 35' +/- North of fence East (RR tie posts) no other evidence of ownership. Found 1965 witnesses #2 and #4.

Found corner accepted as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1997" From Which:

- N89E 41.85 8" Quad Cedar (MDSH tag)
- West 12.92 Aluminum Ogemaw Remon cap
- S19W 37.37 corner post N, S & E (MDSH tag)
- N48W 16.8 center 2" Spruce (no tag)
- S74W 14.32 fence post (MDSH tag)

Approved by Peer Review

11-20-97 TL JLR
DATE INITIALS

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/24/97

