

**SURVEY & REMONUMENTATION**

**MAR 19 1998**

OGEMAW COUNTY REMONUMENTATION

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 2E F-13

T R

T R

T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**LIBER 3 PAGE 138**

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

26 Dec 1997 2:54:12 PM

WANDA MUZIK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Timothy L. Lapham, in a field survey on November 20 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO L. Clason 1837 set post  
B. Ash 10" B23E 35 lk  
W. Pine 24" N19W 46 lk  
Closing corner not set

T. Lapham 1985 Survey (N850326)  
Witnessed to F-1, 21N2E as 1.32' E of F-1

T. Lapham 1992 Survey (N922637) & LCRC (L2, P178)  
Found 1/2" iron

T. Lapham 1993 Survey (N933367)  
Same corner & witnesses as 1992 survey & LCRC

Edmonds Engineering 1974 Survey (L1, P500)

Found 1/2" iron  
S22W 54.0 8" Basswood  
S18E 41.75 5" Maple  
N07E 31.25 fence corner

South 1.8' centerline of road  
S60W 72.09 10" Ash  
N50W 59.08 fence corner  
North 32.32 fence corner  
S25E 41.96 6" Maple

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of GLO corner

Found 2 iron 1.32' apart. East iron is on fence line North and on West edge of cleared land for pipeline North. No evidence of fence line South. Either iron could be on East line of cleared land for pipeline to South. East iron has been used as corner F-13. Two 1974 Edmonds Engineering witnesses found. 1985 and 1992 Lapham witnesses found.

Accepted found iron as best evidence of correct corner position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1997" From Which:

S24W 54.53 10" Basswood  
S24E 41.95 6" Maple  
N02E 32.49 Nail in top centerline post (E, W, N)  
West 1.32 Aluminum Ogemaw Remon cap  
South 1.8' Centerline pavement E & W  
S63W 72.16 14" Oak (was called Ash)  
N57W 59.60 Nail in top centerline fence brace post

Approved by Peer Review

11-20-97 JLR  
DATE INITIALS

Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/24/97

