

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

For corners in

SECTION

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R02E	G-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	



3006781
Page: 1 of 1
12/27/1999 09:09A
L-3 P-290
Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on December 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- G-9: GLO by B.F. Hail, 1846, 10" A. Beech
- N21W 72.76 Tele Pole
- N30E 62.43 16" Basewood
- LCRC by T. Lapham, 1993, Found Pk nail
- S29W 85.20 Power Pole
- N20W 76.20 Cor Post
- N36E 72.20 Cor Post
- Survey by T. Lapham, 1987, Found Pk nail
- North 7 Centerline M-55
- Survey by L. Cavanagh, 1975, Found Pk nail
- County Road Plans, 1987, Found Pk nail
- North 7.5 Centerline M-55
- MDOT Plans by T. Lapham, 1999, Set 1/2"x16" capped iron in mon box
- S28W 25.89m Power Pole
- N44E 21.08m Power Pole
- N26W 23.12m Centerline 4" pipe underground cable marker
- S58E 33.295m Power Pole
- MDOT Plans, 1965+-, No material
- North 7.18 Centerline M-55
- Survey by J. Richardson, 1970+-, Pk reset from highway data
- S28W 85.03 Power Pole

Approved by Peer Review

12/23/99 TLR
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9: No GLO evidence found. Found 1/2" capped iron in monument box. All 1993 and 1999 witnesses found. Corner is PI of curve per MDOT plans. Distance South matches 1970 and 1987 surveys. Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-9: Set 5/8" rerod w/aluminum remon cap
- S28W 84.94 Power Pole
- N44E 69.16 Power Pole
- N26W 75.85 Centerline 4" pipe underground cable marker
- S58E 109.23 Power Pole



Signed by Timothy L. Lapham
Surveyor's Michigan License No. 27595

Date 12/23/1999