

FEB 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ogemaw
(County)

Located in:

Corner Code #

1. Public Land Survey

T22N R02E

G-10

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R



3006779

Page: 1 of 1
12/27/1999 09:09A
L-3 P-288

Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-10: GLO by B.F. Hall, 1846, Post

LCRC by J. Wilcox, 1980, Set Iron
N87W 33.10 Fence Post
S40W 58.69 Fence Post
S84E 31.77 Cor Fence Post
N52E 46.13 Fence Post

S40W 58.69 Fence Post
S84E 31.77 Cor Fence Post
N52E 46.13 Fence Post

LCRC by T. Lapham, 1989, Found 1/2" capped iron
S62E 49.03 NW top cor of AT&T pedestal
S69W 38.33 Steel fence cor post
S65W 43.28 NE cor of phone pedestal at point level w/road

County Road Plans, 1987, Found 1/2" capped iron
N87W 33.10 Fence Post
S40W 58.69 Fence Post
S84E 31.77 Cor Post

Survey by J. Richardson, 1970+-, Set 1/2"x3/8" bar s.p.m.
S46.5W 44.19 Tele Pole
S86.5E 31.74 Fen Post
South 2 Fence Line East

Approved by Peer Review

DATE 12/27/99

INITIALS TLL

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10: No GLO evidence found. 1970, 1980, and 1989 witnesses have common witnesses so all appear to be same corner. Found 1/2" capped iron and 2 - 1989 witnesses. Distances North and South match 1970 and 1987 surveys. Accepted found iron as best evidence of correct position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10: Set 5/8" rerod w/aluminum remon cap
S45E 43.57 4x4 Pipeline Post
S32E 161.85 2" Pine
S56W 42.99 4" Steel Post
S80W 38.08 4" Steel Post



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/1999