

FEB 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R02E	G-11
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____



3006780
Page: 1 of 1
12/27/1999 09:09A
L-3 P-289
Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

N20W 68.66 12" R. Pine

A. Description of original monument and accessories and/or subsequent restoration:

- G-11: GLO by B.F. Hall, 1848, Post
 - S19W 1.15 6" Aspen
 - N63E 72.81 6" W. Pine
- LCRC by J. Wilcox, Set 1/2" iron
 - S53E 25.35 8" Maple
 - N70E 85.62 8" W. Pine
 - N12W 78.12 8" Spruce
 - N75W 35.37 Cor Fen Post
- Survey by J. Wilcox, 1982, 1/2" iron
 - S53E 25.35 8" Maple
 - N70E 85.62 8" W. Pine
 - N12W 78.12 8" Spruce
 - N75W 35.37 Cor Fen Post
- Survey by N. Caldwell, 1974, No material
- Survey by L. Cavanagh, Found R/R Iron
 - N82W 32.11 Power Pole
 - S20E 31.45 8" Maple
- County Road Plans, 1998, Found 1/2" iron bar
 - N72E 100.70 10" Poplar
 - S28E 129.67 NE Cor of house
 - S47W 123.97 8" W. Pine
 - N46W 82.82 8" W. Pine
- Survey by J. Richardson, 1970+-, Found R/R rail
 - S86W 32.73 Tele Pole
 - N16W 68.71 4" N. Pine
 - S36E 31.85 12" Maple
- Survey by T. Lapham, 1987, No material
 - S50E 31.1 Maple Stump
 - N30E 82.5 10" W. Pine
 - N20W 68.66 12" R. Pine
- County Road Plans, 1987, Found 1/2" rerod
 - S50E 31.1 Maple Stump
 - N70E 82.5 10" W. Pine

Approved by Peer Review

12-16-99 TL
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11: No evidence of GLO survey. 1980 Iron reset from 1970 witnesses. 1970, 1976, and 1987 witnesses have common ties. Distance North matches 1970 and 1987 surveys. All surveys appeared to use the same corner. Accepted found 1/2" iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-11: Set 5/8" rerod w/ aluminum remon cap
 - N72E 100.70 10" Poplar
 - S28E 129.67 NE cor of house
 - S32W 70.77 Utility Pole
 - N46W 82.82 8" W. Pine



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/23/1999