

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

QUALITY &  
RECORDS  
FEB 24 2000

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T22N R02E</u>	<u>G-12</u>
2. Property Controlling in Section	T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

SECTION



3006782  
Page: 1 of 1  
12/27/1999 09:09A  
L-3 P-291  
Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

N60W 100.7 7" Birch

G-12: GLO by BF Hall, 1846, found post

N15E 16.1k 12" Hemlock  
N6W 21.1k 8" Birch

County Road Plans, 1999, found 1/2 rod w/cap

N71E 40.19 12" Red Pine  
S16W 88.21 5" Birch  
S66W 47.72 8" Poplar  
N42W 76.92 10" Poplar

LCRC by J. Wilcox, 1980, found iron w/cap  
East 25.27 Iron w/cap  
N80E 17.20 Cor Fence Post  
S83W 44.66 Twin Poplar

Unrecorded survey by L. Cavanagh, 1974, set 1/2"x18" steel bar  
East 25 Iron w/cap

Survey by L. Cavanagh, 1974, found 1/2" bar  
No witnesses

Survey by N. Caldwell, 1974  
No Witnesses

Survey by L. Cavanagh, 1976, found 1/2" bar  
N17E 75.75 8" Birch clump

Approved by Peer Review

12-26-99  
DATE

TL  
INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12: No GLO evidence found. Corner set in 1974 by Cavanagh by S.M.P. Found Cavanagh iron and witnesses from 1974 Cavanagh survey, 1976 survey, 1980 LCRC, and 1999 road plans. Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12: N71E 40.19 12" R. Pine  
S16W 88.21 5" Birch  
S66W 47.72 8" Poplar  
N42W 76.92 10" Poplar  
East 25.00 Iron w/cap

Signed by



Surveyor's Michigan License No. 27595

Date

12/23/1999

