

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
FEB 24 2000

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R02E	H-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SECTION



3006802
Page: 1 of 1
12/27/1999 09:09A
L-4 P-11
Wanda Muzik, Ogemaw Co. Registrar SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-11: GLO by B.F. Hall, 1846, Post
North 32.63 Fence Post
N21W 10 8" Cedar
South 30.34 Fence Post
N60E 13 10" Birch
S70W 58.43 Twin Elm

LCRC by T. Lapham, 1993, Found 1/2" Iron
North 5.7 Centerline of Road
North 32.63 Fence Post
South 30.34 Fence Post
S70W 58.43 Twin Elm

Survey by R. Higgins, 1976, Found 1/2" Iron
No witnesses

Survey by J.L. Wilcox, 1982, No material
Corner at midpoint of G-11 to I-11

Survey by N. Caldwell, 1974, No material

Survey by T. Lapham, 1996, Found 1/2" rod
North 5.7 Centerline of Road

Approved by Peer Review

12-11-99 TLR
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11: No GLO evidence found. Found 1/2" iron and 1 - 1993 witness. 1982 surveys called for corner to be at midpoint of G-11 to I-11. Found iron is very close to midpoint. Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11: Set 5/8"x36" rerod w/aluminum remon cap
S70E 99.72 6" Box Elder
S29W 73.59 14" White Pine
N60W 72.53 12" Triple Maple
N4W 48.21 8" Poplar

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/23/1999