

# SURVEY & REMONUMENTATION

MAR 19 1998

OGEMAW COUNTY REMONUMENTATION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in

<u>Ogemaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>2E</u>	<u>H-13</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

LIBER **3** PAGE **136**  
STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

26 Dec 1997 2:53:23 PM

WANDA MUZIK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Timothy L. Lapham, in a field survey on November 20 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed or below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Clason 1837 set post Hemlock 16" N57E 45 lk Hemlock 14" N11W 10 lk No Closing Corner Set	Ledy 1992 LCRC (L3, P7) Found 1/2" rod SW 66.30 spike in 6" Pine SE 59.95 spike in 18" Pine NNW 44.53 spike in 8" Maple NNE 44.00 spike in 10" Pine
Cavanagh 1974 Surveys (Victor River Acres and 72015A) Corner shown - no witnesses Combined they show dimension to I-13	Ledy 1992 Survey (L6, P254 - 60) Same as LCRC L3, P7 except set rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner.  
Found 1/2" rod - dimension to apparent I-13 (1/2" rod) is 2618.70 - Cavanagh's 1974 surveys show a dimension of 2618.60 so iron matches Cavanagh survey. Found Ledy 1992 witnesses. No other apparent evidence of occupation or corners.  
Accepted the found corner as the best evidence of the correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1997" From Which:  
S48W 66.27 8" Pine  
S46E 59.91 24" Pine  
N16W 44.52 8" Maple  
N35E 44.02 12" Pine  
N03W 33.00 capped iron #21575 (Ledy)  
South 1'+-centerline pavement

Approved by Peer Review  
112047 WJL  
DATE INITIALS

Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/29/97

