

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

SECTION

For corners in

Ogemaw
(County)

Located in:

Corner Code #

1. Public Land Survey

T22N R02E

I-11

T R

T R

T R

T R

T R

T R

T R

2. Property Controlling in Section

S

S

S

S

3. Miscellaneous Property in Sec.

3006783
Page: 1 of 1
12/27/1999 09:09A
L-3 P-292
Wanda Muzik, Ogemaw Co. Register SURC 9.00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11: GLO by B.F. Hall, 1846, Post
S18E 25 8" Cedar
N51W 41 9" Cedar

LCRC by J. Wilcox, 1980, Found rerod w/cap
N52E 54.85 Tele Pole
N43W 52.12 Cor Fence Post
N30W 66.63 Fence Post
S73W 51.7 Stop Sign

LCRC by T. Lapham, 1993, Found 3/4" capped pipe in mon box
N53E 54.85 Tele Pole
N43E 63.46 Fence Cor
N30W 66.63 Fence Post
S73W 49.3 Stop Sign

Survey by R. Higgins, 1976, Reset 1/2" bar from previous info
N50E 54.82 Power Pole
N50W 128.95 Power Pole

Survey by J. Wilcox, 1982, Rod w/ cap
N53E 54.85 Tele Pole
N43W 52.12 Cor Fence Post
N30W 66.63 Fence Post
S73W 51.7 Stop Sign

Survey by T. Lapham, 1996, Found 3/4" capped pipe
N53E 54.85 Tele Pole
N43E 63.46 Fence Cor
N30W 66.63 Fence Post
S73W 49.3 Stop Sign

Approved by Peer Review

12/23/99 JLR
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-11: No evidence of GLO survey. Found witnesses from 1976 survey and 1980 and 1993 LCRC's. All other surveys reference LCRC witnesses. Found 1/2" capped iron matching witnesses. Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11: Set 5/8" rerod w/aluminum remon cap
East 5.1 To centerline Peach Lake Road
N52E 54.81 Utility Pole
S22E 76.55 East End of Culvert
S22W 77.88 West End of Culvert
N70W 104.41 Utility Pole



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/23/1999