

Ogemaw County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

For corners in

SECTION

Ogemaw  
 (County)

Located in:

Corner Code #

1. Public Land Survey

T22N R02E M-1  
 T 22N R 03E A-1  
 T 23N R 02E M-13  
 T 23N R 03E A-13

2. Property Controlling  
 in Section

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
 Property in Sec.

**3006791**  
 Page: 1 of 1  
 12/27/1999 09:09A  
 L-3 P-300  
 Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

GLO by L. Clason, 1838, Post  
 S46W 40 ft 12" Hemlock  
 N37E 43 ft 16" W. Birch

Survey by N. Caldwell, 1979, No Material

Survey by R. Higgins, 1979, Iron in pvmt box

Survey by R. Higgins, 1978, No material  
 (shown in centerline road)

MDOT Plans, No material, corner is P.I.

Consumers Power Survey, 1965+, Found boat spike  
 SW 58.0 Tele Pole  
 NE 37.6 Rd Sign Post

Approved by Peer Review

12-26-99 JLL  
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No GLO evidence found. Found iron in monument box at P.I. of road per MDOT. Corner appears to be same used by all surveys since GLO. Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod w/ aluminum remon cap  
 N34E 120.67 Utility Pole  
 S65E 103.91 NW Cor Block Bldg  
 S35W 98.45 Utility Pole  
 N25W 110.91 Utility Pole  
 West 1.0 Centerline M-33

Signed by [Signature]  
 Surveyor's Michigan License No. 27595

Date 12/23/1999